

1. Component NAVY	FY 2026 SPECIAL PROJECTS PROGRAM			2. Date 2026-27-03
3. Installation(SA) & Location/UIC: M67400 (SH) MARINE CORPS BASE, CAMP SMEDLEY BUTLER (CAMP SCHWAB-6009) HENOKO OKINAWA, JAPAN			4. Project Title Repair Bldg 1024, Armory Expansion & Admin Conversion	
5. Fund Type O&MMC	6. Category Code 14346	7. Project Number BU26PPE70M	8. Project Cost (\$000) 10,412	
9. Cost Estimates				
Item	UM	Quantity	Unit Cost	Cost (\$000)
MULTI PURPOSE BEQ/BOQ/CO HQS - Construction	SF	1	10,412,000.00	10,412
B20 - Exterior Enclosure: CMU infill and weapons port windows, 28 openings total - Construction	LS			(267)
C10 - Interior Construction: vault doors, structural walls, partitions, COMM room, OSS entrance - Construction	LS			(401)
C30 - Interior Finishes: paint, VCT, CT tile, bathroom and OSS finishes, armory spaces - Construction	LS			(190)
D20 - Plumbing: fixture capping, removal, new water fountains, OSS plumbing removal - Construction	LS			(195)
D30 - HVAC: ceiling realign, exhaust, split A/C, DX multi-zone, chillers, TAB - Construction	LS			(1,674)
D40 - Fire Protection: fire hose cabinet replacement, 4 EA per NFPA 10 - Construction	LS			(22)
D50 - Electrical and Communications: IDS/ESS, WAOs, SIPR network, TR, OSP/ISP, lighting mods - Construction	LS			(1,801)
E20 - Furnishings: stainless steel shelves at weapons issue port windows, 11 EA - Construction	LS			(14)
F20 - Selective Demolition: window/door removal, ceiling, OSS gut, ACM mastic per Bhate 2001 - Construction	LS			(432)
G10 - Site Preparation: tree removal, 6 EA at new exterior pad locations - Construction	LS			(19)
G20 - Site Improvements: walkways, landings, concrete pads, covered overhangs, pavilion - Construction	LS			(504)
Contingency - 10% of Construction Subtotal - Construction	LS			(552)
LSH - Life Safety and Health Allowance, 2.5% of iNFADS PRV \$96,523,347 - Construction	LS			(2,413)
Design - Planning and Design, 6% of Construction Base - Construction	LS			(509)
SIOH - Supervision, Inspection and Overhead, 8% - Construction	LS			(679)
CM - Construction Management, 4% of Construction Base - Construction	LS			(339)
DB Design - Design-Build Design, 4% of Total Funded - Construction	LS			(401)

1. Component NAVY	FY 2026 SPECIAL PROJECTS PROGRAM			2. Date 2026-27-03
3. Installation(SA) & Location/UIC: M67400 (SH) MARINE CORPS BASE, CAMP SMEDLEY BUTLER (CAMP SCHWAB-6009) HENOKO OKINAWA, JAPAN			4. Project Title Repair Bldg 1024, Armory Expansion & Admin Conversion	
5. Fund Type O&MMC	6. Category Code 14346	7. Project Number BU26PPE70M	8. Project Cost (\$000) 10,412	
9. Cost Estimates(Continued)				
Item	UM	Quantity	Unit Cost	Cost (\$000)
Subtotal				10,412
Contingency (0.0%)				0
SIOH (0.0%)				0
Total Funded Cost				10,412
Classification of Work Construction				10,412
Special Interest Codes Restoration and Modernization				10,412
Total Project Cost				10,412
Planning and Design (0%) (NON ADD)				(0)
10. Description of Proposed Construction:				
Building 1024 is a multipurpose facility (Primary: Small Arms Storage) built in 1991. After repairs, this building will be in use for a minimum of 20 years. This project provides for the comprehensive renovation of the first floor of Building SCH-1024 to create a consolidated armory complex and support operational facilities and includes the replacement of building-wide end-of-life mechanical systems. A total of five (5) GSA Class 5 vault doors will be procured and installed. The primary scope is the creation of multiple high-security areas. This includes constructing two distinct armory facilities, each secured by two GSA Class 5 vault doors. Within the armories, drop ceilings and bathroom fixtures will be removed, plumbing lines capped, and all ceiling-mounted fixtures realigned. A new multi-zone Electronic Security System (IDS) and new fire hose cabinets will be installed. A separate Open Storage Secret (OSS) area will be established through the complete demolition of the former locker and sauna areas; its entrance will be secured with one GSA Class 5 vault door and require structural reinforcement of the concrete opening. The OSS will be equipped with dedicated HVAC and a lockable SIPRNET enclosure, which will be connected via a new fiber optic run from the main telecom room. A COMSEC storage vault will also be established, secured with a GSA-approved combination lock. Supporting renovations include the conversion of the former gym into new administrative workspaces; the conversion of the laundry room into an admin space; and the establishment of a new indoor weapons cleaning area with dedicated exhaust within the former rec room. The public restroom will be restored with new fixtures, and new water fountains will be installed. Exterior work includes creating new weapons, issuing ports with ballistic-rated windows and metal shelves, while infilling other openings with CMU. To support these				

1. Component NAVY	FY 2026 SPECIAL PROJECTS PROGRAM			2. Date 2026-27-03
3. Installation(SA) & Location/UIC: M67400 (SH) MARINE CORPS BASE, CAMP SMEDLEY BUTLER (CAMP SCHWAB-6009) HENOKO OKINAWA, JAPAN			4. Project Title Repair Bldg 1024, Armory Expansion & Admin Conversion	
5. Fund Type O&MMC	6. Category Code 14346	7. Project Number BU26PPE70M	8. Project Cost (\$000) 10,412	

10. Description of Proposed Construction:(Continued)

ports, new concrete pads and landings, extended walkways with railings, and steel-frame overhead covers will be constructed; additionally, a metal deck with railings will be installed to provide a level surface over a sloped area at one issue port. A new outdoor steel-frame pavilion for weapons cleaning will also be built, requiring associated tree removal and site drainage improvements.

A complete overhaul of the telecommunications infrastructure will be performed, beginning with the removal of all existing first-floor cabling. A new, fully equipped Telecommunications Room will be constructed within the former rec room, complete with a raised floor, racks, UPS, and EPO button. The project will also replace the building's main air-cooled chillers and circulating pumps, followed by a full Test, Adjust, and Balance (TAB) of the HVAC systems on all four floors. The scope includes provisions for the survey and targeted abatement of identified asbestos-containing materials. All work will be performed to meet current UFC, life-safety, and physical security standards. Minor deficiencies identified during the project scope will also be repaired.

11. Requirement:

FACILITY PLANNING DATA: NONE

PROJECT:

The project will provide modernization to Building 1024 on Camp Schwab, Japan to support additional armory and secured administrative space for 4th Marine Regiment (4th MarRegt) and Combat Logistics Battalion 4 (CLB-4).

(Current Mission)

REQUIREMENT:

This project is required to re-establish mission-critical armory and operational facilities for Combat Logistics Battalion 4 (CLB-4) and 4th Marine Regiment (4th MarRegt), preventing a critical capability gap caused by the scheduled demolition of their existing facilities. The project's primary purpose is to construct two distinct, UFC-compliant armories to ensure both units can continue to securely store, issue, and maintain their organic weapons and equipment.

Because this will be an enduring, consolidated facility, it is also a requirement to construct the necessary operational support spaces. This includes an Open Storage Secret (OSS) area to support the classified command and control functions of the tenant units, as well as the administrative offices and dedicated weapons cleaning areas that were integral to the soon-to-be-demolished facilities.

Finally, the project includes the replacement of the building's end-of-life chillers and pumps to sustain the habitability of the entire facility and provide a reliable environment for the new mission-critical functions. This project ensures both forward-deployed units can maintain their "fight tonight" readiness posture without interruption or degradation of capability.

CURRENT SITUATION:

The current situation presents an imminent and unacceptable loss of multiple core capabilities. The existing armories and their associated administrative and support facilities serving both CLB-4 and 4th MarRegt are programmed for demolition as part of a base-wide realignment. As a result of this planned action, the first floor of Building SCH-1024 has been designated for adaptive reuse to serve as the replacement consolidated facility.

However, its current configuration as a barracks residential floor is functionally inadequate for this mission-critical role. The space lacks every required feature for an enduring operational facility: it has no GSA-rated vault doors or reinforced

1. Component NAVY	FY 2026 SPECIAL PROJECTS PROGRAM		2. Date 2026-27-03
3. Installation(SA) & Location/UIC: M67400 (SH) MARINE CORPS BASE, CAMP SMEDLEY BUTLER (CAMP SCHWAB-6009) HENOKO OKINAWA, JAPAN		4. Project Title Repair Bldg 1024, Armory Expansion & Admin Conversion	
5. Fund Type O&MMC	6. Category Code 14346	7. Project Number BU26PPE70M	8. Project Cost (\$000) 10,412

11. Requirement:(Continued)

CURRENT SITUATION:(Continued)

walls suitable for an armory or an Open Storage Secret (OSS) area; it does not contain a suitable layout for administrative offices; and it has no covered, environmentally compliant area for weapons cleaning.

This facility deficiency is compounded by a critical, building-wide infrastructure failure. The building's primary air-cooled chillers and circulating pumps are at the end of their service life, rendering them unreliable and incapable of providing the consistent climate control necessary to sustain operations for the entire four-story facility. This project is therefore required to correct these extensive deficiencies, transforming the residential space into the fully functional facility that both units require while simultaneously restoring the habitability of the entire building.

Facility condition: BCI 80 | MDI 61

FLOODPLAIN: Not sited in floodplain per Okinawa Hazards Map (OUSD memo, 11 Feb 2014).

IMPACT IF NOT PROVIDED:

Failure to fund this project will result in a complete and catastrophic loss of mission-critical capabilities for two forward-deployed combat units. Upon the scheduled demolition of their existing facilities, both Combat Logistics Battalion 4 and 4th Marine Regiment will be left with no compliant or secure location to store, issue, or maintain their organic weapons and equipment. This will render both units combat-ineffective and unable to meet their "fight tonight" readiness posture.

This physical security failure will be compounded by a crippling command and control deficiency. Without the required Open Storage Secret (OSS) area, the units will have no organic space to conduct classified planning or integrate with joint and partner forces.

Furthermore, this entire scenario is set against the backdrop of a failing building-wide HVAC system. The end-of-life chillers are guaranteed to fail, which will render the entire four-story facility uninhabitable due to extreme temperatures and poor air quality, making any attempt to occupy the building unsustainable. Ultimately, inaction is not a viable option; it guarantees a forward-deployed force will lose its armories, its ability to conduct secure C2, and eventually, the habitability of its designated replacement headquarters.

NOTES:

Status of Design: Preliminary Planning
Preliminary Planning. No design contract has been awarded. Delivery is Design-Build (DB) to FEAD.

An Economic Analysis has been prepared in accordance with MCO P11000.5G w/CH-1 & CH-2 and is included as a supporting document to this submission. The estimated Total Project Cost of \$10,413,140 represents 10.8 percent of the facility Plant Replacement Value (PRV) of \$96,523,347, which is below the 75 percent repair limit. The project exceeds the \$7,500,000 threshold under 10 USC 2811(d) and requires congressional notification prior to execution.

83,732 SF, four-story permanent facility; Multipurpose Facility (Primary: Small Arms Storage): CCN 14345, constructed 01-Nov-1991. GOJ-owned (FMRA INGRANT ID 3605)
No major repair since initial construction.

Building 1024 serves as designated administrative space during DPRI-directed

1. Component NAVY	FY 2026 SPECIAL PROJECTS PROGRAM			2. Date 2026-27-03
3. Installation(SA) & Location/UIC: M67400 (SH) MARINE CORPS BASE, CAMP SMEDLEY BUTLER (CAMP SCHWAB-6009) HENOKO OKINAWA, JAPAN			4. Project Title Repair Bldg 1024, Armory Expansion & Admin Conversion	
5. Fund Type O&MMC	6. Category Code 14346	7. Project Number BU26PPE70M	8. Project Cost (\$000) 10,412	

11. Requirement:(Continued)

NOTES:(Continued)

interim consolidation on Camp Schwab. Original Camp Kinser relocation plan revised; both units remain at Camp Schwab pending future realignment. Upon relocation, buildings return to base inventory. Repair investment is justified by current operational requirement and remaining service life regardless of long-term basing disposition.

iNFADS record (RPUID 148675, Facility ID NFA100000443601)

Other Non-Project Costs (If applicable):

The following related projects support the consolidation of 4th Marine Regiment and Combat Logistics Battalion 4 on Camp Schwab under the DPRI program of record (Post G-F Decision, Camp Schwab Projects): BU26PPE71M (PAX 387433), SCH- 3314, Convert to 4th Marine Regiment HQ/UDP West; BU26PPE74M (PAX 387568), SCH-3270, HVAC design; BU26PPE72M (PAX 387624), SCH-3213, Convert to CLB-4 HQ; BU26PPE73M (PAX 387622), SCH-3237, Re-partition Warehouse for Three Units/Telecomm Room with Fire Suppression Design.

Sources of equipment associated with this project from other appropriations are: NONE.

Phasing and Timeline for inter-related projects:

Construction shall prioritize the armory and associated weapons cleaning room, including all supporting electrical, mechanical, fire suppression, physical security infrastructure, and access control systems required to achieve full armory operational capability. This facility is the designated receiving location for consolidated armory operations displaced from Building 3424, which falls within the FRF demolition area and must be vacated prior to 1 June 2028. The armory and all supporting life-safety and security systems within the construction scope shall be substantially complete before displaced armory functions transition from Building 3424. All remaining scope may proceed concurrently but shall not impede armory completion.

Full armory operational capability is also contingent on Intrusion Detection System (IDS) installation and activation, which is executed by the Naval Information Warfare Center (NIWC) through MCIPAC Physical Security and MCICOM coordination and falls outside the construction contract scope. The construction contractor shall provide all conduit, raceway, dedicated power provisions, and supporting physical infrastructure required to support IDS installation. Coordination of IDS installation and activation should be initiated concurrent with construction to prevent delays to armory operational status following construction completion.

ADDITIONAL:

A. Facilities Data: NONE

B. Hazardous Material Information:

An asbestos-containing material survey was conducted at Building 1024 by Bhate Environmental in November 2001. The survey identified one confirmed ACM: H3 floor tile mastic containing 15% Chrysotile across 8,392 linear feet. Scope-triggered targeted abatement of 857 linear feet is included in this project. All abatement work will be performed in accordance with applicable federal and host-nation environmental regulations prior to renovation activities in affected areas.

C. Economic Analysis:

Economic Analysis required per OPNAVINST 11010.20J ☒ (Yes if Checked)
Economic Alternatives Considered:

1. Component NAVY	FY 2026 SPECIAL PROJECTS PROGRAM			2. Date 2026-27-03
3. Installation(SA) & Location/UIC: M67400 (SH) MARINE CORPS BASE, CAMP SMEDLEY BUTLER (CAMP SCHWAB-6009) HENOKO OKINAWA, JAPAN			4. Project Title Repair Bldg 1024, Armory Expansion & Admin Conversion	
5. Fund Type O&MMC	6. Category Code 14346	7. Project Number BU26PPE70M	8. Project Cost (\$000) 10,412	

11. Requirement:(Continued)

ADDITIONAL:(Continued)

- (1) Status Quo:
[Not-Viable]:

The status quo alternative is continuation of the current building configuration without repair or renovation. Under this alternative, the first floor of Building 1024 would remain in its current residential barracks configuration, and no action would be taken to address the end-of-life chiller and circulating pump systems. This alternative is not viable. The scheduled demolition of the existing armory facilities serving both CLB-4 and 4th MarRegt will leave both units without any compliant location to store, issue, or maintain their organic weapons and equipment. The existing building configuration cannot accommodate armory operations, classified storage, or compliant weapons cleaning. Continued deferral of the mechanical system replacement will result in the eventual failure of building-wide climate control, rendering the entire four-story facility uninhabitable. This alternative does not meet the mission requirement and was not carried forward.

- (2) Sustainment/Maintenance:
[Not-Viable]:

The sustainment and maintenance alternative would address only routine upkeep and preventive maintenance of existing building systems without performing the required first-floor renovation or replacing the end-of-life mechanical equipment. While routine maintenance is a programmatic obligation that must continue regardless of project funding, it does not constitute a viable solution to the capability gap created by the demolition of existing armory facilities. Performing maintenance on a residential floor configuration does nothing to establish the required armory, OSS, or administrative spaces. Targeted maintenance of the failing chillers and pumps is no longer cost-effective given their age and condition and would not provide a lasting solution. This alternative does not meet the mission requirement and was not carried forward.

- (3) Restoration/Modernization:
[Viable Project]:

The restoration and modernization alternative is the comprehensive renovation of the Building 1024 first floor to establish a consolidated armory complex, secured operational spaces, and administrative and support facilities, combined with replacement of the building's end-of-life chiller and circulating pump systems. This scope includes installation of five GSA Class 5 vault doors across two armory facilities and one Open Storage Secret area, construction of a COMSEC storage vault, establishment of indoor and outdoor weapons cleaning areas, creation of new administrative workspaces, construction of a new telecommunications room, installation of a new Electronic Security System, and all associated structural, mechanical, electrical, and site work required to bring the facility into compliance with current UFC, life-safety, and physical security standards. This is the only alternative capable of re-establishing the full spectrum of mission-critical capabilities lost through the demolition of existing facilities while simultaneously restoring the habitability and serviceability of the entire four-story structure for a projected minimum service life of 20 years. This alternative is the recommended course of action and is identified as the Minimum Viable Project in the Analysis Results section.

1. Component NAVY	FY 2026 SPECIAL PROJECTS PROGRAM		2. Date 2026-27-03
3. Installation(SA) & Location/UIC: M67400 (SH) MARINE CORPS BASE, CAMP SMEDLEY BUTLER (CAMP SCHWAB-6009) HENOKO OKINAWA, JAPAN		4. Project Title Repair Bldg 1024, Armory Expansion & Admin Conversion	
5. Fund Type O&MMC	6. Category Code 14346	7. Project Number BU26PPE70M	8. Project Cost (\$000) 10,412

11. Requirement:(Continued)

ADDITIONAL:(Continued)

- (4) Lease:
[Not-Viable]:

The lease alternative would involve identifying and leasing off-installation commercial or government-owned space to provide the required armory, classified storage, and administrative functions. This alternative is not viable. The physical security requirements governing small arms storage and Open Storage Secret facilities under applicable DoD and UFC standards cannot be satisfied by commercial or off-installation leased facilities. Classified information handling requirements preclude reliance on non-government-controlled space. Host-nation land use restrictions and SOFA considerations further limit the availability and suitability of off-installation alternatives in Okinawa. This alternative does not meet the mission requirement and was not carried forward.

- (5) New Footprint:
[Not-Viable]

The new footprint alternative would involve constructing a new, purpose-built facility on Camp Schwab to house the required armory, classified storage, and operational support spaces. This alternative is not viable. Building 1024 has already been designated as the replacement consolidated facility under the DPRI-directed interim consolidation plan for Camp Schwab. New construction on this installation is constrained by available land, host-nation land use agreements, and the GOJ-owned status of existing infrastructure under the FMRA program. A new footprint would require significantly greater investment, a longer delivery timeline, and additional MILCON programming actions not supportable within the current program of record. This alternative does not meet cost-effectiveness criteria and was not carried forward.

- (6) Analysis Results:
Five alternatives were considered to address the mission requirement. The status quo, sustainment and maintenance, lease, and new footprint alternatives were each evaluated and not carried forward. The occupying units must vacate their current facilities and be resident in Building 1024 no later than the third quarter of FY 2028. That deadline is driven by the DPRI-directed FRF demolition sequence at Camp Schwab, which requires existing unit facilities to be cleared to make way for decades of follow-on construction including a new runway, aircraft apron, and supporting infrastructure. The demolition line does not flex around unit availability. Status quo and sustainment-only alternatives do not produce a habitable, code-compliant facility capable of supporting the required mission functions. Leasing is not a viable path for classified operational and storage space on a Marine Corps installation in Okinawa. New construction cannot be programmed, designed, and delivered within the available window. The restoration and modernization of Building 1024 is the only alternative that satisfies the mission requirement, complies with applicable UFC, physical security, and life-safety standards, and can be executed within a schedule consistent with the Q3 FY 2028 occupancy requirement.

MINIMUM VIABLE PROJECT (MVP): The restoration and modernization of Building 1024, as scoped, is the minimum viable project. Every scope element included represents the minimum work necessary to establish compliant operations and support functions for the occupying units, restore the building systems required for sustained habitation, and meet applicable code and physical security requirements within the mandated timeframe. No scope element has been included beyond what is operationally required or technically necessary to deliver a code-compliant, enduring solution by the required occupancy date.

D. Phasing (\$000): NONE

1. Component NAVY	FY 2026 SPECIAL PROJECTS PROGRAM			2. Date 2026-27-03									
3. Installation(SA) & Location/UIC: M67400 (SH) MARINE CORPS BASE, CAMP SMEDLEY BUTLER (CAMP SCHWAB-6009) HENOKO OKINAWA, JAPAN			4. Project Title Repair Bldg 1024, Armory Expansion & Admin Conversion										
5. Fund Type O&MMC	6. Category Code 14346	7. Project Number BU26PPE70M	8. Project Cost (\$000) 10,412										
11. Requirement:(Continued) ADDITIONAL:(Continued) E. Other Proposed Projects: F. Status of Design: G. Equipment associated with this project which will be provided from other appropriations: NONE Activity POC: MCBB Planning Phone No: 645-5470 Attachments: Site Plan Detailed Cost Estimate Economic Analysis NEPA Documents BFR (Basic Facility Requirement) Other													
12. Signatures: <table border="0" style="width: 100%;"> <tr> <td style="width: 20%;"><u>Position</u></td> <td style="width: 60%;"><u>Electronic Signature</u></td> <td style="width: 20%;"><u>Date</u></td> </tr> <tr> <td>Public Works Officer</td> <td>Justus OConnor</td> <td>21-Apr-2026</td> </tr> <tr> <td>Branch Chief</td> <td>Bil Hawkins</td> <td>09-Apr-2026</td> </tr> </table>					<u>Position</u>	<u>Electronic Signature</u>	<u>Date</u>	Public Works Officer	Justus OConnor	21-Apr-2026	Branch Chief	Bil Hawkins	09-Apr-2026
<u>Position</u>	<u>Electronic Signature</u>	<u>Date</u>											
Public Works Officer	Justus OConnor	21-Apr-2026											
Branch Chief	Bil Hawkins	09-Apr-2026											